

1 120319

10-5 15-185-20404-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Drill Completion 2/27/72

NE NE NW, SEC. 9, T 22 S, R 13 W/E

4950 feet from S section line

2970 feet from E section line

Soeken-Besthorn

Lease Name _____ Well # 4

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588

County Stafford 117.68

Operator: Woodman-Iannitti Oil Company

Name & Address Box 308

Well Total Depth 3621 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 278

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 12:30 p.m. Day: 5 Month: 10 Year: 19 89

Plugging proposal received from James Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3620' Perfs at 3513-17'

1st plug sand 5 1/2" casing back to 3465' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:30 p.m. Day: 5 Month: 10 Year: 1989

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3465' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 100 sx cement.

Pumping pressure 0-650 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2965.5' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

(if applicable) observe this plugging.

Signed Duane Rankin
(TECHNICIAN)

DATE 10-13-89
26146
INV. NO. _____