

1 120318

10-5 15.185-00341-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 2/17/56
SE NE NW, SEC. 9, T 22 S, R 13 W/E

4290 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6588

Lease Name Soeken-Besthorn Well # 1

Operator: Woodman-Iannitti Oil Company
Name & Address Box 308
Great Bend, KS 67530

County Stafford 123.14

Well Total Depth 3789 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 277

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 11:15 a.m. Day: 5 Month: 10 Year: 19 89

Plugging proposal received from James Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 3780' Perfs at 3510-13'

1st plug sand back to 3460' and dump 5 sx cement on top of sand through bailer,

2nd plug pump in 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 100 sx cement. 10-12-89

RECEIVED STATE CORPORATION COMMISSION

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 5 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3460' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 100 sx cement.

Pumping pressure 0-500 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2390.5' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(void) ~~XXXXXX~~ observe this plugging.

DATE 10-13-89

Signed Duane Rankin (TECHNICIAN)

INV. NO. 26148