

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20081-00-00  
Spot: SE Sec/Twnshp/Rge: 29-26S-40W  
1315 feet from S Section Line, 1302 feet from E Section Line  
Lease Name: BREHM Well #: 1  
County: HAMILTON Total Vertical Depth: 3000 feet

Operator License No.: 32457  
Op Name: ABERCROMBIE ENERGY, LLC  
Address: 10209 W. CENTRAL, STE 2  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2450		
PROD	5.5	2727	0	WITH 185 SX CMT
SURF	8.625	566		WITH 350 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/25/2017 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Revd. from: TIM JULIAN Company: ABERCOMBIE ENERGY Phone: (620) 793-8186

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/25/2017 12:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2450'. PUMP 155 SX CMT FROM 2275' TO 600'. PERFORATE 2 HOLES AT 600'. INJECTION RATE 3/4 BPM AT 1000#. RE-PERF 2 HOLES AT 575'. INJECTION RATE 2 BPM AT 500#. CIRCULATE CMT FROM 575' TO 0' USING 160 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2501	2626		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.


Phigged through: CSG

INVOICED  
MAY 11 2017

District: 01

5-2-17

Signed



(TECHNICIAN)

RECEIVED  
MAY - 2 2017  
KCC DODGE CITY



5A