

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-111-20532-00-00
Spot: SWSESE Sec/Twnshp/Rge: 26-21S-10E
330 feet from S Section Line, 990 feet from E Section Line
Lease Name: FARTHING Well #: 1-A
County: LYON Total Vertical Depth: 2630 feet

Operator License No.: 31772
Op Name: BLACK STAR 231 CORP.
Address: LIVESTOCK EXCHANGE BLDG 1600
KANSAS CITY, MO 64102

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/24/2017 11:00 AM
Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC
Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method:

50' cement plug @ 2500' 50' cement plug @ 1700' 50' cement plug @ 900' 250' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 02/24/2017 2:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

connect to drill pipe,pumped 15 sxs cement @ 2500',pulled pipe to 1700',pumped 15 sxs cement,pulled pipe to 900',pumped 15 sxs cement ,pulled pipe to 250'pumped 100 sxs cement to surface.

Perfs: _____

RECEIVED
KCC DIST # 3
MAY 01 2017
CHANUTE, KS

MH
KCC WICHITA
MAY 05 2017
RECEIVED

INVOICED
MAY 11 2017

Remarks:
Plugged through: DP

District: 03

Signed Mike Heffern
(TECHNICIAN)

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



15-111-20532
Cement or Acid Field Report
 Ticket No. **3267**
 Foreman Steve Neal Guss
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
4-24-17	1069	Farthing #1-A	26	21	10	Lyon	Ks
Customer			Unit #	Driver	Unit #	Driver	
Black Star 231 Corp			109	Alan			
Mailing Address			112	Steve			
1600 Genessee Suite 340							
City	State	Zip Code					
Kansas City	Mo	64102					

Job Type PTA New Hole Depth 2630' Slurry Vol. _____ Tubing _____
 Casing Depth _____ Hole Size 7 7/8 Slurry Wt. _____ Drill Pipe 4 1/2
 Casing Size & Wt. _____ Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting: Plug well as follows
15 sks - 50' plug AT 2500'
15 sks - 50' plug AT 1700'
15 sks - 50' plug A 900'
100 SKS 150' to surface
145 SKS 60/40 Perm mix cement w/ 4% Gel
Job Complete Rig down
Thank you

KCC WICHITA
MAY 05 2017
RECEIVED

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-103	1	Pump Charge	1050.00	1050.00
C-107	35	Mileage	3.95	1382.5
C-203	145 SKS	60/40 permix cement	12.75	1848.75
C-206	500 #	Gel 4%	.20	100.00
C-108-A	6.24	Ton Mileage Bulk Truck	MIK	34500
			SubTotal	3482.00
			7.50% Sales Tax	261.16
Authorization <u>Call by Dave Farthing</u> Title <u>Toolpusher</u>			Total	3628.16

590 < 181.41 >
 @ 3446.15

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.