

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-21015-00-00
Spot: SWSENE Sec/Twnshp/Rge: 36-10S-17W
2970 feet from S Section Line, 990 feet from E Section Line
Lease Name: WHISMAN F Well #: 2
County: ROOKS Total Vertical Depth: 3560 feet

Operator License No.: 5042
Op Name: EDMISTON OIL COMPANY, INC.
Address: 125 N MARKET STE 1420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3559		250 SX
SURF	8.625	209		125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/12/2017 8:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: SHANNON RAYBERN Company: EDMISTON OIL COMPANY, INC. D Phone: (620) 792-6924

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Production perforations: 3146' - 3391'.
Tubing parted at 1850' - 1900'.

Plugging Proposal Received By: PAT BEDORE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/12/2017 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perforated at 1112'. Ran tubing to 1850' and pumped 175 sx cement w/400 # hulls. Pulled tubing to 1150' and pumped 25 sx cement w/100 # hulls to circulate to surface. Pulled tubing to surface. Topped off 4 1/2" casing with 5 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 25 sx cement. Shut in pressure 200 psi.

GPS: 39.14158N -099.16225W

Perfs:

Top	Bot	Thru	Comments
3367	3391		
3269	3274		
3243	3248		
3146	3152		

KCC WICHITA
MAY 02 2017
RECEIVED

Remarks: COPELAND ACID AND CEMENT

Plugged through: TBG

INVOICED
MAY 11 2017

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

2017
APR 18 2017