

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-165-21738-00-00
Spot: SEWNESW Sec/Twnshp/Rge: 11-18S-18W
2157 feet from S Section Line, 3330 feet from E Section Line
Lease Name: ALEX Well #: 1
County: RUSH Total Vertical Depth: 3860 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3854	0	WITH 125 SX CMT
SURF	8.625	1232		WITH 425 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2017 8:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Revd. from: JEFF WERTH Company: H-D OILFIELD SERVICE, INC. Phone: (785) 798-7677

Proposed Plugging Method: SAND BOTTOM 50' ABOVE OPEN HOLE & 5 SX CMT. PLUG AT 1240' WITH 50 SX CMT. PLUG AT 620' WITH 40 SX CMT. PLUG AT 260' WITH 50 SX CMT. TOP OFF WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/19/2017 11:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED TO 3750' WITH 5 SX CMT. CASING PARTED 8' DOWN WHEN PULLING STRETCH ON CASING. WAS ABLE TO RUN PACKER & TESTED CASING TO 500# & HELD. PERFORATED AT 1240'. RUN PACKER TO 240' & SET IT. PUMPED 250 SX CMT. CIRCULATED TO SURFACE. PULLED PACKER & HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
3854	3860		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

INVOICED

Plugged through: TBG

MAY 11 2017

District: 01

5-2-17

Signed Michael Maier

(TECHNICIAN)

RECEIVED
MAY - 2 2017
KCC DODGE CITY

MP

FA