

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-03869-00-00
Spot: SWNW Sec/Twnshp/Rge: 14-17S-11W
3300 feet from S Section Line, 4620 feet from E Section Line
Lease Name: BLOOMER B Well #: 4
County: BARTON Total Vertical Depth: 3325 feet

Operator License No.: 33186
Op Name: LB EXPLORATION, INC.
Address: 2135 2ND RD
HOLYROOD, KS 67450

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3300		0 SX
SURF	8.625	242		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/13/2017 12:00 AM
Plug Co. License No.: 34032 Plug Co. Name: SIEMSEN WELL SERVICE INC.
Proposal Rcvd. from: MICHAEL PETERMANN Company: LB EXPLORATION, INC. DBA Phone: (785) 252-8034

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 13 sx gel. Well has been squeezed from 504' to surface. Cement in braden head.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/13/2017 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400' and 660'. Ran tubing to 3200' and pumped 50 sx cement w/100 # hulls. Pulled tubing to 2720' and pumped 13 sx gel. Pulled tubing to 1400' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 700'. Circulated cement to surface with 65 sx cement. Pulled tubing. Topped off with 5 sx cement pressured to 200 psi.

GPS: 38.57446 -098.51479

Perfs:

Top	Bot	Thru	Comments
3300	3325		
3055	3237		
2850	2853		

Remarks: GLOBAL CEMENTING

Plugged through: TBG

KCC WICHITA
MAY 02 2017
RECEIVED

INVOICED
MAY 11 2017

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

CM

APR 19 2017

Form CP-2/3