

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-25821-00-01  
Spot: NENWSESE Sec/Twnshp/Rge: 1-16S-23W  
1300 feet from S Section Line, 924 feet from E Section Line  
Lease Name: THOMPSON Well #: 1-1  
County: NESS Total Vertical Depth: 4462 feet

Operator License No.: 5144  
Op Name: MULL DRILLING COMPANY, INC.  
Address: 1700 N WATERFRONT PKWY BLDG 12  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4310		
PC		1786		CMT TO SURFACE
PROD	5.5	4453	0	WITH 150 SX CMT
SURF	8.625	213		WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/25/2017 1:30 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Revd. from: KYLE RANDA Company: MULL DRILLING Phone: (316) 264-6366

Proposed Plugging Method: PUMP BOTTOMT WITH 50 SX CMT & 100# HULLS. GEL APCER. CIRCULATE CMT FROM 1800' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/25/2017 3:15 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

TIED ONTO BACKSIDE & PRESSURED TO 200# WITH 15 SX CMT. PUMP RATE WAS ESTABLISHED AT 2.5 BPM AT 1200#. TIED ONTO THE 5 1/2" CASING & PUMPED 50 SX CMT WITH 100# HULLS. GEL SPACER TO 1800' THEN 175 SX CMT. PRESSURED TO 2000#.

Perfs:

Top	Bot	Thru	Comments
4346	4358	CSG	
3990	3992	CSG	

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

INVOICED  
MAY 11 2017

District: 01

Signed [Signature] (TECHNICIAN)

RECEIVED  
APR 27 2017  
KCC DODGE CITY