

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-26170-00-00
Spot: SWNENWNE Sec/Twnshp/Rge: 32-16S-12W
473 feet from N Section Line, 1692 feet from E Section Line
Lease Name: LAWRENCE JACOBS Well #: 1
County: BARTON Total Vertical Depth: 3462 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	386		180 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/18/2017 12:00 AM
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC
Proposal Rcvd. from: SID Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RAY DINKEL Witness Type: NONE
Date/Time Plugging Completed: 04/18/2017 5:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

1st plug @3350 w/50 sx
2nd plug @815 w/50 sx
3rd plug @450 w/100 sx
4th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

KCC WICHITA
MAY 02 2017
RECEIVED

Remarks: GLOBAL
Plugged through: DP

INVOICED
MAY 11 2017

District: 04

Signed Ray A Dinkel
(TECHNICIAN) cm

APR 24 2017