

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-171-21199-00-00  
Spot: SWSNWSW Sec/Twnshp/Rge: 11-20S-34W  
1564 feet from S Section Line, 798 feet from W Section Line  
Lease Name: BERL Well #: 1  
County: SCOTT Total Vertical Depth: 4945 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH ST  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	208		WITH 165 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/28/2017 9:30 AM  
Plug Co. License No.: 33575 Plug Co. Name: WW DRILLING, LLC  
Proposal Rcvd. from: SID DEUTSCHER Company: WW DRILLING, LLC Phone: (785) 743-6774

Proposed Plugging Method: 1ST PLUG AT 2260' WITH 50 SX CMT. 2ND PLUG AT 1200' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: NONE  
Date/Time Plugging Completed: 04/28/2017 11:30 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

1ST PLUG AT 2260' WITH 50 SX CMT. 2ND PLUG AT 1200' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 240' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

INVOICED  
MAY 11 2017

District: 01

Signed Larry Harris - ECPS  
(TECHNICIAN)

5A

RECEIVED  
MAY - 2 2017  
KCC DODGE CITY