

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-03745-00-00  
Spot: SWSE Sec/Twnshp/Rge: 2-17S-11W  
660 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: F F BURMEISTER B Well #: 3  
County: BARTON Total Vertical Depth: 3386 feet

Operator License No.: 30458  
Op Name: RJM COMPANY  
Address: PO BOX 256  
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3375		150 SX
SURF	8.625	295		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/02/2016 9:00 AM  
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.  
Proposal Rcvd. from: CHRIS HOFFMAN Company: RJM CO. Phone: (620) 587-3600

Proposed Plugging Method: Ordered 400 sx common cement w/500 # hulls.  
Operator ran in with a bit and scraper and got to bottom of well. Pulled out and tried to run a liner and it stopped at 630'.  
Milled on the spot for 3 days and could not get back through the bad spot in the casing and decided to plug well.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/06/2016 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 300'. Ran tubing to 600' and pumped 125 sx cement. No circulation of cement. Shut down. Mixed 75 sx cement w/3% cc and pumped cement. No returns. Shut down for 2 hours. Pumped 100 sx cement. No returns. Shut down for the weekend.  
09/06/2016- Tagged cement at 150'. Ran tubing. Circulated cement to surface with 25 sx cement. Pulled tubing. Tied on to surface pipe and pumped 75 sx cement. Circulated cement up casing.

GPS: 38.59627 -098.50539

Perfs:

Top	Bot	Thru	Comments
3375	3386		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

INVOICED  
MAY 11 2017

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

SEP 21 2016

SEP 28 2016

Form CP-2/3

CONSERVATION DIVISION  
WICHITA, KS