

LEASE NAME Brakey

WELL NUMBER 1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 12 TWP. 21 RGE. 32W (E) or (W)

COUNTY Finney

Date Well Completed

Plugging Commenced 3-7-97

Plugging Completed 3-11-97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR American Warrior, Inc.

ADDRESS P. O. Box 399 Garden City, KS 67846

PHONE (316) 275-2963 OPERATORS LICENSE NO. 4058

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on (date)

by (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 2725'

Show depth and thickness of all water, oil and gas formations.

3-27-97

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 325' | none |
| | | | | 4 1/2 | 2713' | 600' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from feet to feet each side. Halliburton pumped 300# hulls and 20 sks cement on bottom. Top of cement 2200'. Shot casing at 1400', did not come loose. Casing leak @ 300'. Ran tubing to 320', pressured to 1000#. Ran tubing to 1400' and spotted 20 sks cement. Pulled up to 930' & circulated clean. Pulled tubing, shot csg at 705', not loose. Shot at 600', pumped 30 sks cement. Pulled to 350', pumped 40 sks cement. Pulled rest of csg & topped with 15 sks cement. Plugging complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: American Warrior, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) *Mike Kelso*

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 26th day of March, 19 97

James S. [Signature]
 Notary Public

My Commission Expires:

