


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kearney County. Sec. 28 Twp. 21S Rge. 35W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner Shallow Water Refining Company
Lease Name Shuereman Well No. 1
Office Address Box 11320, Kansas City, Mo.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 12-23-65 19
Application for plugging filed 12-22-65 19
Application for plugging approved 12-22-65 19
Plugging commenced 12-22-65 19
Plugging completed 12-23-65 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving for Hugh E. Scott, Sublette
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5075 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 8 5/8" | 400' | none |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 650', spotted 25 sks. cem. through drill pipe
Spotted 25 sks. cem. @ 400', set plug @ 40' with 15 sks. cem.

1-3-66
RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

P. O. Box 486, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of December, 19 65

My commission expires April 1, 1967

Ulanda Nichols
Ulanda Nichols
Notary Public.

DRILLER'S LOG

COMPANY: Shallow Water Refining Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: SHUEREMAN #1
 LOCATION: C SW NE Sec. 28-21S-35W
 KEARNEY COUNTY, KANSAS
 COMMENCED: 11-18-65
 COMPLETED: 12-23-65

| | | | |
|------|-------------|--------------------------|---------------|
| 0 | 5 | Topsoil | |
| 5 | 35 | Clay | |
| 35 | 44 | Shale | |
| 44 | 140 | Chalk | |
| 140 | 400 | Shale | |
| 400 | 750 | Shale | |
| 750 | 1400 | Shale, Redbed | |
| 1400 | 1675 | Sand | |
| 1675 | 2140 | Shale, Shells | |
| 2140 | 2155 | Anhydrite | |
| 2155 | 2785 | Shale, Shells | |
| 2785 | 3210 | Shale, Lime | |
| 3210 | 3350 | Lime | |
| 3350 | 3600 | Lime, Shale | |
| 3600 | 3890 | Shale, Lime | |
| 3890 | 4331 | Lime, Shale | |
| 4331 | 4400 | Lime | |
| 4400 | 4550 | Lime, Shale | Core #1 4400' |
| 4550 | 5075 | Lime | to 4450' |
| | <u>5075</u> | <u>RTD - D. & A.</u> | Core #2 4450' |
| | | | to 4500' |
| | | | Core #3 4500' |
| | | | to 4550' |

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 3 1966
 CONSERVATION DIVISION
 Wichita, Kansas

Kelly's Water Well set 400' of 8 5/8" surface casing with 300 sacks Posmix, 1% cc Plug Down 11-18-65

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Shuereman #1 well, located C SW NE Section 28, Township 21 South, Range 35 West, Kearney County, Kansas, as reflected by the files of Leben Drilling, Inc., and of Kelly's Water Well Service.

Leslie Kite

 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 30th day of December, 1965.

Ulanda Nichols

 Ulanda Nichols

My Commission Expires:
 April 1, 1967