

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.--82-3-117

API NUMBER 15-009-156962000

LEASE NAME NW Beaver Unit

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER T8-WI

330 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. TWP. RGE. (E) or (W)

COUNTY Barton

Date Well Completed 12-2-42

Plugging Commenced 6-1-88

Plugging Completed 6-16-88

LEASE OPERATOR N.C.R.A.

ADDRESS Box 6, Great Bend, Kansas 67530

PHONE# 316-793-8771 OPERATORS LICENSE NO. 5565

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Four (4)

Is ACO-i filed? If not, is well log attached? With application

Producing Formation Depth to Top Bottom T.D. 3320'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				9"	555'	None
				5-1/2"	3314'	1,745.04'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 2850' and 5 sacks cement. Shot casing at 2,500' 2400', 2100', 1900' and 1700'. Pulled 55 joints of 5-1/2" casing. Allied squeezed well with 25 sack ATL cement and 500# hulls blended in 175 sacks cement. Maximum pressure was 400 psi and shutin 150 psi.

RECEIVED
 STATE CORPORATION COMMISSION

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Gt. Bend, Ks. 67530

JUN 7 1988

STATE OF Kansas COUNTY OF Barton, ss.

06-07-88
 CONSERVATION DIVISION
 Wichita, Kansas

James W. Rockhold (Employee of Operator) or Wichita, Kansas (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 14th day of June, 1988

My Commission Expires

STATE NOTARY PUBLIC
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 7-26-91


Iona M. Leatherman
 Notary Public

TRANSWESTERN OIL CO.
 Depiebbe No. 1.

S.M.C. 6 T. 16 R. 12 W
 C.S.L. SW SE

Total Depth. 3320'
 Comm. 11-18-42 Comp. 12-2-42
 Shot or Treated.
 Contractor. Iron Drlg. Co.
 Issued. 3-6-43

County. Barton



CASING:
 9" 555' Con.
 5 1/2" 3315' Con.

Elevation.

Production. Pot. 160 BO, 8HW
 Physical

Figures Indicate Bottom of Formations.

shale & shells	190
shale & sand	265
sand	290
shale	362
sand	455
sand & shale	490
shale & shells	510
red rock	530
shale & shells	555
shale & red rock	790
anhydrite	817
red bed & shale	1200
salt & shale	1428
shale & shells	1530
lime	1590
shale	1620
lime & shale	2105
sdv lime & shale	2225
shale & shells	2363
shale	2485
lime sdy	2525
shale	2575
shale & lime	2777
lime	2812
lime & shale	2833
lime brkn	2875
lime	2930
lime & shale	3015
shale	3039
lime	3238
lime sft	3295
conglomerate & chert	3316
lime	3320
Total Depth.	

K. G. S. LIBRARY

Tops:
 Anhydrite 790
 Topeka 2695?
 Lansing 3019
 Conglomerate 3291
 Arbuckle 3312