

STATE OF KANSAS
STATE CORPORATION COMMISSION

15-009-06508-8000
WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton

County. Sec. 6 Twp. 16S Rge. 12 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE SW SE

Lease Owner Franco Central Oil Company

Lease Name Depiesse Well No. 7

Office Address 750 Fourth National Bank Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Salt Water Disposal

Date well completed 10-1-49 19

Application for plugging filed 1-6-1958

Application for plugging approved 1-15-1958

Plugging commenced 5-8-1959

Plugging completed 5-8-1959

Reason for abandonment of well or producing formation
Well would not take water

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation Arbuckle Depth to top 3311 Bottom 3468 Total Depth of Well 3468 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Arbuckle	water	3330	3468	8-5/8"	508'	None
				5-1/2"	3330'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mud and scale from 3468' to 800'
Filled with 275 sacks cement from 800' to surface
2" tubing was run to depth of 489' and cement was circulated to surface

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Shirer Well Service
Address Gorham, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.
L. M. Clothier (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) L. M. Clothier
750 Fourth National Bank Bldg., Wichita, Kans.
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of May, 1959

Elaine Wilkening Notary Public.

My commission expires 4-14-60
RECEIVED
STATE CORPORATION COMMISSION

MAY 15 1959
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 6 T. 16 R. 12
BOOK PAGE 276 LI-E 6

WELL LOG

#7 Depiesse
Co. - Franco Central Oil Co.
Contr. - Phillips & Hanson

170' North of South Line
315' East of West Line of
SE $\frac{1}{4}$ Section 6-16-12W,
Barton County, Kansas

Comm: 9-12-49
Comp: 9-25-49

soil & sand rock	40
shale, shells & sand	265
shale, shells & red rock	508
red rock	600
red bed	795
anhydrite	830
shale & shells	1105
shale, shells & salt	1240
shale & shells	1405
shells	1440
lime & shale	1500
lime	2175
lime & shale	2679
lime	3467

T.D.

RECEIVED
STATE CORPORATION COMMISSION
JAN 14 1958
CONSERVATION DIVISION
Topeka, Kansas

CASING RECORD:

8 5/8" set at 508' w/250 sacks cement.

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS

We hereby affirm that the above is a true and correct copy of the driller's log of the #7 Depiesse located in the SE $\frac{1}{4}$ of Section 6-16-12W, Barton County, Kansas.

PHILLIPS & HANSON

By Ray R. Hanson

Subscribed and sworn to before me, this 18th day of October, 1949.

Eleanor R. Notary
Notary Public

My Commission expires April 14, 1952.

PLUGGING
FILE SEC. 6 T. 16 R. 12W
BOOK PAGE 76 LINE 6