

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
100 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-083-10188-00-00  
API NUMBER Comp 1963

LEASE NAME Goebel East Unit

WELL NUMBER H-2

810 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 13 TWP. 21S RGE. 24W (E) or (W)

COUNTY Hodgeman

Date Well Completed \_\_\_\_\_

Plugging Commenced 7-16-01

Plugging Completed 7-17-01

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

EASE OPERATOR Pickrell Drilling Co., Inc.

ADDRESS 100 S. Mian, Suite 505, Wichita, Ks. 67202

PHONE# (316) 262-8427 OPERATORS LICENSE NO. 5123

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on \_\_\_\_\_ (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4489'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	205	None
				5-1/2"	4488'	240'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each side. Plugged off bottom with sand to 4410' and 5 sacks cement. Shot pipe @700', pumped 80 sks. cement, shot pipe @240', pulled up to 220', pumped 40 sks. cement, pulled up to 40' and pumped 20 sks. cement. 60/40 pos. 10% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P. O. Box 467 Chase, KS 67524

RECEIVED 8-6-01

1 AUG -> 6 2001  
SUBSCRIBED AND SWORN TO before me this 3rd. day of August XK9 2001

KCC WICHITA

Irene Herzberg  
Notary Public

My Commission Expires: \_\_\_\_\_



Form CP  
Revised 05-

OR