

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado De. by Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15.083-10190-0000

API NUMBER N/A

LEASE NAME Goebel East Unit

WELL NUMBER H-4

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 13 TWP. 21S RGE. 24W (E) or (W)

COUNTY Hodgeman

Date Well Completed         

Plugging Commenced 12-27-94

Plugging Completed 12-29-94

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Pickrell Drilling Co., Inc.

ADDRESS P.O. Box 375 Ness City, Ks. 67560

PHONE# (913) 798-2430 OPERATORS LICENSE NO. 5123

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on          (date)

by Richard Lacy (KCC District Agent's Name).

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 4496'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size   | Put In | Pulled out |
|-----------|---------|------|----|--------|--------|------------|
|           |         |      |    | 8 5/8" | 271'   | none       |
|           |         |      |    | 4 1/2" | 4479'  | none       |
|           |         |      |    |        |        |            |
|           |         |      |    |        |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid wa placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set  
Sanded bottom to 4425' and ran 4 sacks cement. Shot @700'. hooked to backside and took injection rate. hooked to 4 1/2" casing and mixed 100 sacks 60/40 6% gel. Max pressure 400# Shut In 50# Hooked to backside and mixed 100 sacks 60/40 6% gel. Max Pressure 200# Shut In 50#.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529 1-5-95

Address P.O. Box 209 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or Operator above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed: that the same are true and correct, so help me God.

(Signature) Mike Kelso

(Address) P.O. Box 209 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 31 day of December, 19 94

Irene Herzberg  
Notary Public

My Commission Expires:  
USE ONLY ONE SIDE OF EACH FORM



Form CP-1  
Revised 05-88

RECEIVED  
STATE CORPORATION COMMISSION

JAN 05 1995

INQUIRY DIVISION