

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-083-20054-0001

LEASE NAME Wright

WELL NUMBER CB #1

SPOT LOCATION NW NE

SEC. 31 TWP. 21S RGE. 24W (E) or (W)

COUNTY Hodgeman

Date Well Completed _____

Plugging Commenced 4-16-86

Plugging Completed 4-21-86

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Phillips Petroleum Company

ADDRESS Rt. 3 Box 20-A Great Bend, Kansas 67530

PHONE # (316) 793-8421 OPERATORS LICENSE NO. 5229

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 4580'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	524'	none
				5-1/2"	4577'	2406'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 4430' and 5 sacks cement. Shot pipe @3000', 2710', 2406' and pulled a total of 57 joints (2406') of 5-1/2" casing. Plugged surface with 4 hulls, 15 gel, 50 cement, 1 hull, 10 gel, 150 cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address P.O. Box 347 Chase, Kansas 67524

4-29-86

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 28 day of April, 19 86

My Commission expires: _____



Irene Hoover
Notary Public

RECEIVED
STATE CORPORATION COMMISSION
APR 29 1986
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

COMPANY
CONTRACTOR
FARM
LOCATION

COMMENCED
COMPLETED

Beardmore Drilling Company
Phillips Petroleum Co.
~~Beardmore Drilling Company~~
LEBEN DRILLING, INC.
WRIGHT B-1
C NW NE SECTION 31-21S-24W
HODGEMAN COUNTY, KANSAS
9-28-68
10-9-68

0	524	Shale, Sand
524	675	Shale, Shells
675	1596	Redbed, Sand
1596	1630	Anhydrite
1630	1820	Shale, Shells
1820	2305	Shale
2305	2567	Shale, Lime Streaks
2567	2610	Lime
2610	2820	Shale, Lime
2820	3480	Lime, Shale
3480	3800	Shale
3800	4075	Lime, Shale
4075	4580	Lime
	<u>4580</u>	<u>RTD - D. & A.</u>

Washed down by Phillips Petroleum Co. 4-10-81

8 5/8" 24# used surface casing set @ 524' cemented with 275 sacks
Common cement, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is
a true and correct copy of the log of the Wright B-1 Well, located
C NW NE of Section 31, Township 21 South, Range 24 West, Hodgeman
County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
COUNTY OF BARTON) SS

Subscribed and sworn to and before me, a Notary Public, in
and for Barton County, Kansas, this 14th day of October, 1968.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
April 1, 1971

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1966

CONSERVATION DIVISION
Wichita, Kansas