


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Hodgeman County. Sec. 31 Twp. 21S Rge. (E) 24 (W)
Location as "NE/CNW%SW%" or footage from lines C NW NE
Lease Owner Beardmore Drilling Company
Lease Name Wright Well No. B-1
Office Address 700 - 120 Building, Wichita Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 10-9 1968
Application for plugging filed 10-9 1968
Application for plugging approved 10-9 1968
Plugging commenced 10-9 1968
Plugging completed 10-9 1968
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4580 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	524'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged with 70 sacks cement @ 720'
Plugged with 20 sacks cement @ 480'
Plugged with 10 sacks cement @ 40'

10-16-68

RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite

(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of October, 1968

My commission expires April 1, 1971

Ulanda Nichols

Notary Public.

DRILLER'S LOG

COMPANY	Beardmore Drilling Company
CONTRACTOR	LEBEN DRILLING, INC.
FARM	WRIGHT B-1
LOCATION	C NW NE SECTION 31-21S-24W HODGEMAN COUNTY, KANSAS
COMMENCED	9-28-68
COMPLETED	10-9-68

0	524	Shale, Sand
524	675	Shale, Shells
675	1596	Redbed, Sand
1596	1630	Anhydrite
1630	1820	Shale, Shells
1820	2305	Shale
2305	2567	Shale, Lime Streaks
2567	2610	Lime
2610	2820	Shale, Lime
2820	3480	Lime, Shale
3480	3800	Shale
3800	4075	Lime, Shale
4075	4580	Lime
	<u>4580</u>	<u>RTD - D. & A.</u>

8 5/8" 24# used surface casing set @ 524' cemented with 275 sacks
Common cement, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Wright B-1 Well, located C NW NE of Section 31, Township 21 South, Range 24 West, Hodgeman County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1968
CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 14th day of October, 1968.

Ulanda Nichols

Ulanda Nichols

My Commission Expires:
April 1, 1971