

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-093-20661-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Osborn Heirs Company OPERATOR'S LICENSE NO. 5249 ^{6/96}

ADDRESS P. O. Box 17968, San Antonio, Texas PHONE # (210) 826-0700
78286

LEASE (FARM) John WELL NO. 1A WELL LOCATION SW/4 COUNTY Kearny

SEC. 9 TWP. 21S RGE. 38W (X) or (W) TOTAL DEPTH 3050 PLUG BACK TD 3047

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8-5/8 SET AT 335 CEMENTED WITH 300 SACKS

CASING SIZE 5-1/2 SET AT 3048 CEMENTED WITH 700 SACKS

PERFORATED AT 2894-2914 & 2946-2970

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Plug by filling 5-1/2" casing with cement from total depth to surface, using sufficient hulls to block perforations at 2894-2970'. Fill 5-1/2" x 8-5/8" casing annulus from surface with additional cement as necessary. Cut casings and weld plate over well at a depth below ground level as to not interfere with cultivation..

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN approx. 8:00 am, May 10, 1996
or when approved

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: 4-15-96

Dale Taylor PHONE # (316) 373-2701 RECEIVED
KANSAS CORPORATION COMMISSION

ADDRESS P. O. Box 307, Kendall, Kansas 67857

PLUGGING CONTRACTOR To be bid Allied Cementing LICENSE NO. APR 15 1996

ADDRESS _____ PHONE # () _____ CONSERVATION DIVISION
WICHITA, KS

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Nancy A. FitzSimon
(Operator or Agent) Nancy A. FitzSimon

DATE: 4-12-96



Kansas Corporation Commission

Bill Graves, Governor Timothy E. McKee, Chair Susan M. Seltsam, Commissioner John Wine, Commissioner
Judith McConnell, Executive Director David J. Heinemann, General Counsel

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

April 15, 1996

Osborn Heirs Company
P O Box 17968
San Antonio TX 78286

John 1A
API 15-093-20,661-0000
SW/4
Sec. 09-21S-38W
Kearny County

Dear Dale Taylor,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City, KS 67801
(316) 225-6760