



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION APR 2 - 1974 CONSERVATION DIVISION Wichita, Kansas 412174

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Flemmons of Galaxy has this

date requested permission to plug the following described well:

Mr. Flemmons guarantees payment of the plugging fee.

Operator's full Name: Galaxy Oil Company

Complete Address: 918 Lamar Street, Wichita Falls, Texas

Lease Name: Beymer Well No. 1

Location: C NE NE Sec. 22 Twp. 21 Rge. 37 XX (E)(W)

County: Kearny Total Depth 2775' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flemmons was instructed to plug the well as follows:

10 3/4" to 329' circulated w/ cement. 7" to 2652' cemented.

No Perforations, Open hole 2652' to 2775'

Plug bottom w/ 7" Bridge Plug set at 1200' w/ 6 Feet cement on top of plug.

Mud 1194' to 600' Spot 150 sacks cement 600' to 300'

Mud 300' to 10' Bridge & 5 sacks cement 10' to 0'.

Very truly yours,

[Signature] Conservation Division Agent