



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

12-19-72
RECEIVED
STATE CORPORATION COMMISSION
DEC 19 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Unruh of Abercrombie has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling Inc.

Complete Address: 801 Union Center, Wichita, Kansas

Lease Name: Pfeiffer Well No. 1

Location: C N/2 SW Sec. 9 Twp. 21 Rge. 35 (E)(W)

County: Kearny Total Depth 5036' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

8 5/8" to 365' circulated w/ cement. 5 1/2" to 4704' cemented.

Top perforations 4470' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4400' Mud 4400' to 700'

Spot 50 sacks cement 700' to 550' Mud 550' to 350'

Spot 40 sacks cement 350' to 250' Mud 250' to 45'

Plug, HULLS & 15 sacks cement 45' to 0'.

Very truly yours,

Edgard J. Eves
Conservation Division Agent