



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1964
7-20-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Lang of R.W. Lang has this

date requested permission to plug the following described well:

Mr. Lang guarantees payment of the plugging fee.

Operator's full Name: R.W. Lang

Complete Address: Box 1034 Garden City, Kansas

Lease Name: Lang-Campbell Well No. # 7

Location: NW NW SE Sec. 9 Twp. 21 Rge. (E) (W) 35

County Kearney Total Depth 5035' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lang was instructed to plug the well as follows:

8 5/8"-345' Circulated w/cement. 4 1/2"-4630' Cemented.

Plug back to 4603' Top perforations 2718'

Plug bottom w/20 Sax.cement. ton cement 2600' Mid 2600' to 340'

Spotted 35 Sax.cement 340' to 240' Mid 240' to 45'

Plug, 15 Sax.cement. 45' to 0

Very truly yours,

Conservation Division Agent