



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1972

CONSERVATION DIVISION
Wichita, Kansas

11-15-72

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Holmstrom of KNNG has this

date requested permission to plug the following described well:

Mr. Holmstrom guarantees payment of the plugging fee.

Operator's full Name: Kansas Nebraska Nat Gas Co Inc.

Complete Address: Box 608, Hastings, Nebraska

Lease Name: Martin Well No. 1

Location: App C E/2 W/2 Sec. 23 Twp. 21 Rge. 41 (E) (W)

County: Hamilton Total Depth 2795' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Holmstrom was instructed to plug the well as follows:

7" to 365' circulated w/ cement. 4 1/2" to 2795' cemented.

Top perforations 2778' Plug bottom w/ 15 sacks cement .


Top of cement 2595' Mud 2595' to 600'

Spot 30 sacks cement 600' to 500' Mud 500' to 425'

Spot 30 sacks cement 425' to 300' Mud 300' to 45'

Plug, Hulls & 10 sacks cement 45' to 0'.

Very truly yours,


Conservation Division Agent