



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 28 1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

CONSERVATION DIVISION
Wichita, Kansas

9-28-64

Dear Sir:

Mr. Sargent of Excelsior Oil Corporation has this
date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Excelsior Oil Corporation

Complete Address: 300 N. St. Joseph Avenue. Hastings, Nebraska

Lease Name: F. Miller Well No. # 1

Location: C SE Sec. 32 Twp. 21 Rge. 35 (E)(W)

County Kearney Total Depth 2716' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8"-333' Circulated w/cement. 5 1/2"-2700' Cemented. Perforations 2658' to 2666'

Plug bottom w/20 Sax. cement top cement 2521' Mud 2521' to 350'

Spotted 35 Sax. cement 350' to 250' Mud 250' to 45'

Plug, 15 Sax. cement 45' to 0

Very truly yours,

[Signature]
Conservation Division Agent