



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

RECEIVED  
STATE CORPORATION COMMISSION

APR 15 1974

CONSERVATION DIVISION  
Wichita, Kansas

4-15-74

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Shively of J.A. Allison has this

date requested permission to plug the following described well:

Mr. Shively guarantees payment of the plugging fee.

Operator's full Name: JA. Allison et al

Complete Address: 200 W. Douglas, Wichita, Kansas

Lease Name: Gaskey Well No. 1

Location: C NE NW Sec. 33 Twp. 21 Rge. 35 (E) (W)

County: Kearny Total Depth 5015' Oil Well

Gas Well  Input Well  SWD Well  D & A.  Lost Hole

Mr. Shively was instructed to plug the well as follows:

8 5/8" to 244' circulated w/ cement. Mud 5015' to 700'

Spot 35 sacks cement 700' to 600' Mud 600' to 244'

Spot 35 sacks cement 244' to 144' Mud 144' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent