



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1972
CONSERVATION DIVISION
Wichita, Kansas

3-23-72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Lacy of Beardmore has this

date requested permission to plug the following described well:

Mr. Lacy guarantees payment of the plugging fee.

Operator's full Name: Beardmore Oil Inc.

Complete Address: 700-120 Bldg., Wichita, Kansas

Lease Name: Nuss "D" Well No. 1

Location: NWSE Sec. 3 Twp. 21 Rge. 25 (SE) (W)

County: Hodgeman Total Depth 4483' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lacy was instructed to plug the well as follows:

8 5/8" to 290' circulated w/ cement. Mud 4483' to 800'

Spot 80 sacks cement 800' to 500'. Mud 500' to 290'

Spot 30 sacks cement 290' to 190' Mud 190' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent