



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 9 1968
 CONSERVATION DIVISION
 Wichita, Kansas

12-9-68

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Cook of Imperial Oil Co. has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company Inc.

Complete Address: 780 Fourth Nat'l Bldg., Wichita, Kansas

Lease Name: Bitter "B" Well No. 1

Location: C SE ^{NE} NW Sec. 2 Twp. 21 Rge. 26 (E) (W)

County: Hodgeman Total Depth 4410' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

- 8 5/8" to 265' circulated w/ cement. Mud 4410' to 900'
- Spot 100 sacks cement 900' to 550' Mud 550' to 260'
- Spot 30 sacks cement 260' to 160' Mud 160' to 40'
- Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Edgar J. Eves
 Conservation Division Agent