



15-083-10325-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 13 1968  
CONSERVATION DIVISION  
Wichita, Kansas

9-13-68

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Unruh of El Dorado Supply Company has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: El Dorado Supply Company

Complete Address: 764 Oil Hill Road, Eldorado, Kansas

Lease Name: Lee "S" Well No. 2

Location: C SW NW Sec. 26 Twp. 21 Rge. 25 (W) (W)

County Hodgeman Total Depth 4579' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Unruh was instructed to plug the well as follows:

8 5/8" to 258' circulated w/ cement, 5 1/2" to 4555' cemented

No Perforations Plug bottom w/ sand & 5 sacks cement.

Top of cement 4500' Mud 4500' to 800'

Spot 100 sacks cement 800' to 450' Mud 450' to 250'

Spot 30 sacks cement 250' to 160' Mud 160' to 30'

Plug, Hulls & 10 sacks cement 30' to 0'.

Very truly yours,

Edward J. Edlin  
Conservation Division Agent