



15-083-10324-0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 13 1968
CONSERVATION DIVISION
Wichita, Kansas

9-13-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Unruh of El Dorado Supply has this
date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Eldorado Supply Company

Complete Address: 764 Oil Hill Road, El Dorado, Kansas

Lease Name: Lee "S" Well No. 1

Location: C NW NW Sec. 26 Twp. 21 Rge. 25 ~~(E)~~ (W)

County Hodgeman Total Depth 4584' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Unruh was instructed to plug the well as follows:

8 5/8" to 257' circulated w/ cement. 5 1/2" to 4574' cemented.

No perforations Plug bottom w/ sand & 5 sacks cement.

Top of cement 4520' Mud 4520' to 800'

Spot 100 sacks cement 800' to 450' Mud 450' to 250'

Spot 30 sacks cement 250' to 160' Mud 160' to 30'

Plug, Hulls & 10 sacks cement 30' to 0'.

Very truly yours,

Conservation Division Agent