



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 17 1964

CONSERVATION DIVISION
Wichita, Kansas

9-17-64

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Henshaw of Union Oil Co. Of Calif. has this

date requested permission to plug the following described well:

Mr. Henshaw guarantees payment of the plugging fee.

Operator's full Name: Union Oil Co. Of Calif.

Complete Address: 619 West Texas Ave. Midland, Texas

Lease Name: Kuhlman Well No. # 1-9

Location: APP C SW. NE 1900' FNL. 1980' FEL. Sec. 9 Twp. 21 Rge. 36 (E) (W)

County Kearny Total Depth 5160' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Henshaw was instructed to plug the well as follows:

8 5/8"-653' Circulated w/cement.

Mud 5160' to 4600' Spotted 50 Sax. cement 4600' to 4450'

Mud 4450' to 750' Spotted 50 Sax. cement 750' to 600'

Mud 600' to 62' Plug, Hulls, 25 Sax. cement 62' to 0

Very truly yours,

[Signature]
Conservation Division Agent