



15-093-30003-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

8-11-65  
RECEIVED  
STATE CORPORATION COMMISSION

AUG 11 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Herb Morrell of Earl F. Wakefield has this

date requested permission to plug the following described well:

Cleary Petroleum

Mr. Morrell guarantees payment of the plugging fee.

Operator's full Name: Cleary Petroleum, Incorporated.

Complete Address: 310 Kermac Building, Oklahoma City, Okla.

Lease Name: Rupp Well No. 2

Location: CNE-SW Sec. 5 Twp. 21 Rge. (E)(W)38

County Kearney Total Depth 5150 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Morrell was instructed to plug the well as follows:

302' --8 5/8" Surface pipe, cement circulated with 250 Sx.

Circulate hole with heavy mud, set plug @ 660' & 20 Sx. cement.

"	"	315'	with $\frac{1}{2}$ sk. hulls &
			25 Sx. cement.
"	"	40'	with $\frac{1}{2}$ sk. hulls &
			10 Sx. cement.

Very truly yours,

*N. L. Nichols*

Conservation Division Agent