

State of Kansas



15-093-20002-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

300 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
NOV 27 1961
11-27-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Liles of Pan American Petro. has this
date requested permission to plug the following described well:

Mr. Liles guarantees payment of the plugging fee.

Operator's full Name: Pan American Petroleum Corporation

Complete Address: Box 432, Liberal, Kansas 67901

Lease Name: G. B. Reneker Well No. 1

Location: G SW NW Sec. 4 Twp. 21 Rge. 38 (E) (W)

County Kearny Total Depth 5010' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Liles was instructed to plug the well as follows:

8 5/8" to 1025' circulated w/ cement. 4 1/2" to 5002' cemented

Top perforations 4116' Plug bottom w/ 20 sacks cement

Top of cement 3750' Mud 3750' to 700'

Spotted 35 sacks cement 700' to 600' Mud 600' to 45'

Plug, Halls & 15 sacks cement 45' to 0'

Very truly yours,

Edgar J. Cress
Conservation Division Agent