

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-42-3-117

API NUMBER 15-083-21,402-0000

LEASE NAME Sinclair #1-19

WELL NUMBER 1-19

2310 FT. from S Section Line

2310 FT. from E Section Line

SEC. 19 TWP. 21S (C.E. 25 ~~XX~~ or (W))

COUNTY Hodgeman

Date Well Completed 10-17-93

Plugging Commenced 10-17-93

Plugging Completed 10-17-93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR RANKEN ENERGY CORPORATION

ADDRESS 601 N. Kelly, St 103 Edmond, OK 73003-4855

PHONE (316) 653-7368 OPERATORS LICENSE NO. 3447

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on October 16, 1993 (date)

by Steve Pfeifer (KCC District Agent's Name)

is ACO-1 filled? by operator If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom T.D. 4425'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
surface		0	206	8 5/8"	206	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from foot to foot each section.

50 sx. @ .1560', 80 sx. @ 800', 40 sx. @ 230', 10 sx. @ 40', 15 sx. in rathole
TOTAL 195sx. Halliburton Cementing

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address R.R. 1 Box 183 B Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ranken Energy Corporation STATE CORPORATION COMMISSION

STATE OF Kansas COUNTY OF Barton, ss.

Greg Davidson (Employee of Operator) or ~~(Contractor)~~

above-described well, being first duly sworn on oath, says: That I have read the above-
 statements, and matters herein contained and the log of the above-described well, and that
 the same are true and correct, so help me God.


(Signature) Greg Davidson

(Address) R.R. 1 Box 183 B Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 18th day of October, 1993

Bessie M. DeWerff
 Notary Public

My Commission Expires: 5-20-97 Bessie M. DeWerff



DRILLER'S WELL LOG

DATE COMMENCED: 10-08-93
DATE COMPLETED: 10-17-93

RANKEN ENERGY CORPORATION
SINCLAIR #1-19
NW NW SE SEC. 19-T21S-25W
HODGEMAN COUNTY, KS.

0 - 207 Shale & Post Rock
207 - 735 Sand & Shale
735 - 1470 Shale & Sand
1470 - 2300 Shales
2300 - 4220 Lime & Shale
4220 - 4425 Lime
4425 RTD
4425 LTD

ELEVATION: 2331 GR 2336 KB

SURFACE CASING:

8 5/8" set at 206' W/135 sx. 60/40
Pozmix, 2% Gel, 3% CC


A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON)^{ss}

GREG DAVIDSON of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

Greg Davidson
Greg Davidson

Subscribed and sworn to before me this 21st day of October, 1993.



Bessie M. DeWerff
Notary Public: Bessie M. DeWerff

My Commission expires: 5-20-97

RECEIVED
STATE CORPORATION COMMISSION
OCT 25 1993
CONSERVATION DIVISION
Wichita, Kansas