


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 2 Twp. 21S Rge. 26 (E) W (W)
Location as "NE/CNW/SW" or footage from lines. SE SW
Lease Owner Petroleum Management, Inc.
Lease Name Sinclair Well No. 1
Office Address 1515 Wichita Plaza, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed January 1, 1969
Application for plugging filed January 1, 1969
Application for plugging approved January 1, 1969
Plugging commenced January 1, 1969
Plugging completed January 1, 1969
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4410 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	287.58'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug #1 set @ 800'
Cemented w/80 sx. common.
Plug #2 set @ 290'
cemented w/ 30 sx. cement
Plug #3 set @ 40'
cemented w/10 sx.
5 sx in rathole.

STATE CORPORATION COMMISSION
WICHITA, KANSAS
RECEIVED
JAN 8 1969
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Kansas 67202

1-8-69


STATE OF Kansas, COUNTY OF Sedgwick, ss.
Norman E. Klein (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Norman E. Klein
1720 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 6th day of January, 1969

My commission expires 10-25-72

Gloria Sawcett
Notary Public.



DRILLERS LOG

No. 1 Sinclair

CASING RECORD: 8 5/8" @ 294'
w/175 sx. cement

COMPANY: Petroleum Management, Inc.

CONTRACTOR: Red Tiger Drilling Co.

COMMENCED: December 18, 1968

COMPLETED: January 1, 1969

DESCRIPTION: SE SW
2-21S-26W
Hodgeman County,
Kansas

ELEVATION:

TOTAL DEPTH: 4410'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sod Sand	0	40	
Post Rock Shale	40	296	
Shale & Shells	296	630	
Shale	630	700	
Red Bed Shale	700	990	
Blaine	990	1006	
Shale & Shells	1006	1095	
Sand	1095	1310	
Shale	1310	1365	
Shale & Shells	1365	1607	
Anhydrite	1607	1614	
Shale & Shells	1614	1710	
Shale, Red Bed	1710	1850	
Shale & Shells	1850	1975	
Shale & Lime	1975	2365	
Shale & Shells	2365	2565	
Lime & Shale	2565	3320	
Shale & Lime with Chalk	3320	3701	
Lime & Shale	3701	3780	
Lime	3780	4154	
Lime & Shale	4154	4192	
Lime	4192	4275	
Lime & Shale	4275	4329	
Lime	4329	4410	

RECEIVED
STATE CORPORATION COMMISSION
JAN 8 1969
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Norman E. Klein
Norman E. Klein

Subscribed and sworn to before me this 6th day of January, 1969.

Blaine Dawcett
Notary Public

My Commission Expires:

10-25-72