

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

## WELL PLUGGING RECORD

NORTH

	SEC. 26		

Locate well correctly on above  
Section Plat

HODGEMAN County, Sec. 26 Twp. 21s Rge. 6 (E) 25(W)  
Location as "NE/CNW/SE" or footage from lines. C SW NE  
Lease Owner. PETROLEUM, INC.,  
Lease Name. WRIGHT "J" Well No. 4  
Office Address. ROUTE #2, GREAT BEND, KANSAS  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed. JULY 24 1964  
Application for plugging filed. JULY 24 1964  
Application for plugging approved. JULY 24 1964  
Plugging commenced. JULY 24 1964  
Plugging completed. JULY 24 1964  
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production. 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well HUGH SCOTT  
Producing formation. Depth to top. Bottom. Total Depth of Well 4523 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	425'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

MUDDERED UP WITH HEAVY MUD TO 700', FOLLOWED BY A WOODEN PLUG AND 20 SACKS CEMENT. MUDDERED UP HEAVY MUD TO 400', FOLLOWED BY A WOODEN PLUG AND 20 SACKS CEMENT. MUDDERED UP WITH HEAVY MUD TO 40', FOLLOWED BY A WOODEN PLUG, 1/4 SACK HULLS AND 10 SACKS CEMENT TO BASE OF WELL CELLAR.

RECEIVED  
STATE CORPORATION COMMISSION

AUG 3 1964  
8-3-64  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor. GARVEY DRILLING COMPANY  
Address. ROUTE #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.  
MONTE CHADD (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. MONTE CHADD, DIST. PROD. SUPT.  
(Signature)

ROUTE #2, GREAT BEND, KANSAS  
(Address)

SUBSCRIBED AND SWORN TO before me this 30TH day of JULY, 1964

My commission expires APRIL 14, 1967

Notary Public.

## WELL LOG

15-083-10176-0000

COMPANY Petroleum, Inc.

SEC. 26 T. 21S R. 25W

FARM Wright

NO. J-4

LOC. App C-SW-NE

TOTAL DEPTH 4523'


COUNTY Hodgeman

COMM. 7-10-64

COMP. 7-24-64.

CONTRACTOR Garvey Drilling Company

CASING 8 5/8" @ 425' w/250 sx



ELEVATION 2399' DF

PRODUCTION D &amp; A

FIGURES INDICATE BOTTOM OF FORMATIONS

330' Surface soil and Blue Shale  
425' Shale  
490' White Sand  
770' Shale  
1000' Red Bed  
1020' 1st Anhydrite  
1370' Sand  
1605' Shale and Sand  
1630' 2nd Anhydrite  
2368' Shale and Lime Streaks  
2520' Lime and Shale Streaks  
3130' Lime and Shale  
3202' Lime  
3483' Shale and Lime  
3605' Brown Lime and Chalk Streaks  
3776' Shale and Lime  
3850' Lime and Shale  
4170' Lime  
4196' Shale and Lime  
4510' Lime  
4523' Lime and Chert  
4523' RTD

RECEIVED  
STATE CORPORATION COMMISSION

AUG 3 1964

CONSERVATION DIVISION  
Wichita, KansasState of KansasCounty of Barton

SS

I, Sam N. Stephens of Garvey Drilling Companyupon oath state the above and foregoing is a true and correct copy of the log of the Wright J-4 well.Subscribed and sworn to before me this 29th day of July 19 64My Commission Expires: April 14th, 1967  
NOTARY PUBLIC