

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Osborn Heirs Company

ADDRESS P. O. Box 17968, San Antonio, TX 78286

PHONE# (210) 826-0700 OPERATORS LICENSE NO. 5249

Character of Well gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 4/15/96 (date)

by District I, Kevin Strube on location \_\_\_\_\_ (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? \_\_\_\_\_

Producing Formation Council Grove Depth to Top 2894 Bottom 3050 T.D. 3050

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Chase	gas & water @ 2602	0	335	8-5/8	335'	none
Council Grove	gas & water @ 2894	0	3048	5-1/2	3048'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from    feet to    feet each set.

Filled 5-1/2" casing from total depth to 3' with 500 lbs hulls & 225 sacks 60/40 pozmix cement with 6% gel, density 13.8 ppg. Pressured to 100 psi. Mixed 35 sacks additional and filled 5-1/2" x 8-5/8" annulus. Pressured to 300 psi. Cut casings at 3 ft below ground. Welded plate on top.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. \_\_\_\_\_

Address P. O. Box 420, Ness City, KS 67560-0420

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Osborn Heirs Company MAY 02 1996

STATE OF TEXAS COUNTY OF BEXAR, ss. 5-2-96


NANCY A. FITZSIMON

(Employee of Operator WICHTA (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Nancy A. Fitzsimon

(Address) P. O. BOX 17968, SAN ANTONIO, TX 78286

SUBSCRIBED AND SWORN TO before me this 29TH day of APRIL, 19 96



My Commission Expires 12/22/97

Yolanda Nunley  
 Notary Public

W.B. OSBORNJohn 1-A Well  
Kearny County, KansasOPERATIONS COMMENCED: 11/29/79  
OPERATIONS COMPLETED: 12/4/79DRILLING LOG

11/29	0 - 335	Sand
11/30	335 - 1017	Sand, Shale, Lime
12/1	1017 - 2185	Sand, Shale, Lime
12/2	2185 - 2880	Shale, Lime
12/3	2880 - 3050	Shale, Lime

CASING RECORD

11/29	Ran 8 jts. of new 8-5/8", 24# casing. Set @ 330'.
11/30	Cemented with 225 sacks Class H, 3% C.C. Re-cement on outside of surface pipe with 75 sacks Class H.
12/4	Ran 72 jts. of new 5-1/2", 14# casing. Set @ 3048'. Cemented with 500 sacks Howco light and 200 sacks 50/50 pozmix, 18% salt.

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 15 1996

CONSERVATION DIVISION  
WICHITA, KS