


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Finney County. Sec. 29 Twp. 21S Rge. 34 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C/ SE/4
Lease Owner Michaelis Drilling Company
Lease Name HAFlich Well No. 1
Office Address 1019 East Second Street, Wichita 7, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11/21/55 19
Application for plugging filed 4/16/56 19
Application for plugging approved 4/17/56 19
Plugging commenced 4/20/56 19
Plugging completed 4/22/56 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle Rives
Producing formation Winfield Depth to top 2630 Bottom ? Total Depth of Well 2647 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Shale & Sand		0	291'	8-5/8"	291'	Cement Circulated

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back w/crushed rock from 2647-2600, Dumped 5 sacks cement @ 2600' w/bailer. Top cement 2570'. Filled hole w/mud to 290', Set rock bridge, Dumped 20 sacks cement. Top of cement 230'. Filled hole w/mud to 35'. Set rock bridge, dumped 10 sacks cement for cap.

4-28-56
RECEIVED
STATE CORPORATION COMMISSION

APR 28 1956

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Miller Casing Pulling Company
Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

W. A. Michaelis, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. **MICHAELIS DRILLING COMPANY**

(Signature) W. A. Michaelis, Jr. Managing Partner

1019 East Second Street,
Wichita, Kansas.

SUBSCRIBED AND SWORN TO before me this 27th day of April, 1956.

Mary L. Barnes
Notary Public.

My commission expires 11/7/57.

PLUGGING
FILE SEC 29 T 21 R 34W
BOOK PAGE 54 LINE 5

COPYNO. 1 HAELICHWell Record

Location: C/ SE/4 Sec. 29-21S-34W
 Finney County, Kansas

Commenced: Oct. 21, 1955
 Completed: Oct. 25, 1955

Operator: Michaelis Drilling Company
 1019 East Second Street
 Wichita 7, Kansas

Elevation: 2989' DF
 2986' Gr

Contractor: Michaelis Drilling Company
 1019 East Second Street
 Wichita 7, Kansas

Casing Record: 8-5/8" @ 291' w/200 sacks cement
 5-1/2" @ 2630' w/300 sacks cement

LOG

Clay	49
Sand w/Clay	109
Sand	167
Black shale	228
Black & Blue Shale	293
Blue Shale	1000
Red Bed & Shale	1833
Anhydrite & Red Bed	2100
Anhydrite & Shale	2632' RTD

Herrington	2534
Upper Krider	2560
Lower Krider	2584
Winfield	2629

STATE OF KANSAS)
) ss.
 COUNTY OF SEDGWICK)

The undersigned, MICHAELIS DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

MICHAELIS DRILLING COMPANY

By W. A. Michaelis, Jr.
 W. A. Michaelis, Jr.

Subscribed and sworn to before me
 this 7th day of November, 1955.

Mary L. Bamer

My commission expires: 11/7/57.

RECEIVED
 STATE DEPARTMENT OF CONSERVATION
 NOV 21 1955
 CONSERVATION DIVISION
 WICHITA, KANSAS

PLUGGING
 FILE SEC 29 T 21 R 34W
 BOOK PAGE 54 LINE 5