

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Finney County, Sec. 29 Twp. 21S Rge. (E) 33 (W)

Location as "NE/CNW/SW" or footage from lines 1980' FSL & 1980' FEL
Lease Owner Skelly Oil Company
Lease Name Betts "B" Well No. 1
Office Address 1860 Lincoln Street, Denver, Colorado 80203
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 9, 1972
Application for plugging filed April 10, 1972
Application for plugging approved April 9, (Verbal) 1972
Plugging commenced April 9, 1972
Plugging completed April 9, 1972
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Edgar Eves, Box "F", Sublette, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4800 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Dry Hole						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged back w/mud 4,800' to 798'
Spotted 35 sacks 50-50 Pozmix plug 798' to 724'
Drilling Mud 724' to 32'
Capped w/15 sacks 50-50 Pozmix 32' to Surface
Well Plugged and Abandoned and rig released April 9, 1972.

RECEIVED
STATE CORPORATION COMMISSION
MAY 15 1972
CONSERVATION DIVISION
Wichita, Kansas

5-15-72

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address P. O. Box 1164, Great Bend, Kansas

STATE OF COLORADO, COUNTY OF DENVER, ss.
A. H. Hurley (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *A. H. Hurley*
1860 Lincoln Street, Denver, Colorado 80203
(Address)

SUBSCRIBED AND SWORN to before me this 9th day of May, 1972

My commission expires November 4, 1973

Geroldini Pate
Notary Public.


WELL LOG

COMPANY **Skelly Oil Company**
 FARM **Betts 'B'** NO. **1**
 TOTAL DEPTH **4802'**
 COMM. **3-23-72** COMP. **4-9-72**
 CONTRACTOR **Garvey Drilling Company**

SEC. 29 T. 21S R. 33W

LOC. NW SE

COUNTY **Finney, Kansas**



CASING
10 3/4" @ 805' w/500sx

ELEVATION

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

- 250' Sand & Clay
- 740' Shale & Sand
- 809' Shale
- 995' Shale & Shells
- 1080' Sand & Shale
- 1370' Shale & Sand
- 1490' Shale
- 2620' Shale & Lime
- 2725' Lime & Shale
- 2910' Shale & Lime
- 3095' Lime & Shale
- 3940' Lime
- 4802' Lime
- 4802' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 7 1972
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas }
 County of Barton } ss

I, Charlene Marker of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Betts 'B' #1 well.

Subscribed and sworn to before me this 10th day of April 19 72

My Commission Expires: July 8, 1974

Charlene Marker
James A. [Signature]
 NOTARY PUBLIC