

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Finney County. Sec. 24 Twp. 21 Rge. 33 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW/4 NW/4 SW/4

Lease Owner Salina Drilling Corporation

Lease Name G. E. Gano Well No. 1

Office Address 801 No. 10th Salina, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 5-31-53 19

Application for plugging filed 6-1-53 19

Application for plugging approved 6-1-53 19

Plugging commenced 6-1-53 19

Plugging completed 6-1-53 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand	Water	20	165	8 5/8	275'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Circulated heavy mud half way out of hole--pushed wooden plug to 270' and run 20 sacks cement through 9 joints of drill pipe--filled hole with heavy mud to 140'--pushed wooden plug to 140' and anchored with wire. Run 10 sacks cement filling hole to cellar floor.

RECEIVED
STATE CORPORATION COMMISSION

JUN 5 1953

6-5-53

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Salina Drilling Corporation

Address 801 North 10th, Salina, Kansas.

STATE OF Kansas, COUNTY OF Saline, ss.

Elmer Rider (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Elmer Rider

Box #566, Salina, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of June 19 53

My commission expires 9-28-54

John L. Ford
Notary Public.

PLUGGING
FILE SEC 24 T 21 R 334
BOOK PAGE 105 LINE 15

ROTARY DRILLERS LOG

G. E. Gano #1

Elevation: Laughlin-Simmons
D.F. 2890 KB 2893 GL 2888

NW/4 NW/4 SW/4 sec. 24, Twp.21,
R 33W, Finney County, Kansas.

Operator: Salina Drilling Corporation, Inc.
801 N. 10th,
Salina, Kansas.

Casing Record: 8 5/8"---275'
200 sacks cement. Cement
circulated

Well Commenced: 5-6-53
Well Completed: 6-1-53

Contractor: Salina Drilling Corporation, Inc
801 N. 10th, Salina, Kansas.
Geologist: Don Smith, Wichita, Kansas.

Figures Indicate Bottom of Formations K.B.

Cellar, Base & Rotary Table	8	Lime & Shale	3005
Clay	20	Lime	3185
Sand	165	Lime & Shale	3285
Shale & Shells	275	Lime	3380
Shale	865	Lime & Shale	3600
Sand & Shale	920	Lime	3960
Shale & Shells	1100	Lime & Shale	4005
Shale & Shells-Red Bed	1125	Lime	4385
Red Bed	1550	Lime & Shale	4425
Sand	1760	Lime	4540
Shale & Red Bed	1960	Lime & Shale	4580
Shale & Shells	2210	Lime	4604
Shale & Lime	2500	Lime & Shale	4665
Shale	2600	Lime	4708
Red Bed & Anhydrite	2655	Lime & Shale	4730
Lime-Shale	2665	Shale	4770
Dolomite	2672	Shale-Sand Streaks	4800
Shale	2685	Lime	4820
Dolomite	2700	Shale-Sand Streaks	4840
Lime & Shale	2755	Lime	4960
Lime	2790	Lime-Shale Streaks	4982
Lime	2805	Lime	5000 T.D.
Lime & Shale	2905		

Tops as Picked by Geologist

Topeka	3592	Marmanton	4437
Heebner	3883	Fort Scott	4543
Lansing	3913	Cherokee	4557
Base of Lansing	4415	Mississippi	4777

The above Rotary Driller's Log is complete and correct to the best of my knowledge.

SALINA DRILLING CORPORATION, CONTRACTOR.

Loren W. Hallam
By Loren W. Hallam, President.

RECEIVED
STATE COMMISSION
JUN 15 1953

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 24 T 21 R 33W
BOOK PAGE 105 LINE 15