

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-20754-00-00
Spot: E2W2NW Sec/Twnshp/Rge: 29-21S-37W
1320 feet from N Section Line, 1300 feet from W Section Line
Lease/Unit Name: ELLA Well Number: 1
County: KEARNY Total Vertical Depth: 3050 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

Production Casing Size: 5.5 feet: 3050 WITH 600 SX CMT
Surface Casing Size: 8.625 feet: 322 WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 10/24/2003 11:15 AM

Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: SET CIBP @ 2600'. BAIL 2 SX CMT ON PLUG. LOAD HOLE WITH WATER. BOND LOG CASING. RUN TUBING TO 1100'. CIRCULATE CMT TO SURFACE WITH 100 SX CMT. PRESSURE TEST 8 5/8" X 5 1/2" ANNULUS WITH 50 SX CMT.

Plugging Proposal Received By: RICHARD LACEY

WitnessType: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 10/24/2003 11:45 AM

KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PBTD 3050'. PERFS AT 2633-3006'. PUMPED DOWN 5 1/2" WITH 500# HULLS & 222 SX CMT. CMT FELL TO 160'. SHUT IN. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS WITH 15 SX CMT. PRESSURED UP TO 500#. TOPPED OFF WITH 28 SX CMT.

RECEIVED
OCT 31 2003
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed _____

Kevin D Strube

(TECHNICIAN)

Form CIP-33
[Handwritten signature]