

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-20711-00-00
Spot: CSW Sec/Twnshp/Rge: 16-21S-37W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease/Unit Name: MARVIN Well Number: 1
County: KEARNY Total Vertical Depth: 2806 feet

Operator License No.: 5249
Op Name: OSBORN HEIRS COMPANY, LTD
Address: PO BOX 17968
SAN ANTONIO, TX 78217

Conductor Pipe: Size _____ feet: 97.20
Surface Casing: Size 8.625 feet: 341 WITH 250 SX CMT
Production: Size 5.5 feet: 2806 WITH 700 SX CMT
Liner: Size _____ feet: _____

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/25/2002 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: RICHARD GEIER Company: OSBORN HEIRS Phone: (210) 826-0700

Proposed Plugging Method: FILL 5 1/2" CASING WITH CMT. CHECK BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/25/2002 10:30 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2800'. PERFS AT 2672-2797'. 09/18/02: SET CIBP @ 2650' WITH 5 SX CMT ON TOP. 09/23/02: PRESSURE TESTED CASING TO 500#. 09/25/02: RAN BOND LOG. TOC @ 76'. PERFORATED AT 1025'. PUMPED DOWN 5 1/2" CASING 90 SX CMT. MAXIMUM PRESSURE 1000#. SHUT IN PRESSURE 500#. PUMPED CMT DOWN 8 5/8" X 5 1/2" ANNULUS 10 SX CMT. PRESSURED UP TO 500#. SHUT IN.

RECEIVED
KANSAS CORP COMM
2002 OCT -4 P 1:43

10-4-02

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Kevin D. Strube
(TECHNICIAN)

INVOICED

SEP 30 2002

DATE 10-7-02
INV. NO. 2003060609

Form 01-23