

To: 1 080118
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-093-20,650-0000

NW NW SE NW, SEC. 22, T. 21 S, R. 35 ~~W~~

TECHNICIAN'S PLUGGING REPORT
Operator License # 5855



3890 feet from S section line
3890 feet from E section line

Operator: Wallace Oil & Gas, Inc.
Name & Address: 3030 NW Expressway
Oklahoma City, OK 73112

Lease Name Van Doren Well # 1
County Kearny 91.13

Well Total Depth 2804 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 614

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor H & K Plugging & Salvage License Number 31705

Address P.O. Box 2742, Pampa, TX 79066-2742

Company to plug at: Hour: 9 a.m. Day: 17 Month: 4 Year: 19 97

Plugging proposal received from Dennis Holman

(company name) H & K Plugging & Salvage (phone) 806-665-2550

were: 4 1/2" at 2803' w/250 sx cement, CIBP @ 2700', Perfs at 2725-32, 2786-96, 2660-64, 2670-73'

1st plug set CIBP at 2610' with 2 sx cement on top,

2nd plug at stub with 50 sx cement,

3rd plug at 650' with 75 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None 4-22-97

Operations Completed: Hour: 12 p.m. Day: 17 Month: 4 Year: 19 97

ACTUAL PLUGGING REPORT ^{4/16-} 1st plug set CIBP at 2610' with 2 sx cement on top,

2nd plug shot casing at 685' and pumped 90 sx cement through 2 3/8" tubing, pulled tubing.

3rd plug 4/17/97-ran tubing to 410', tagged cement, and pumped 15 sx cement at 40'.

Remarks: Used common cement by H & K. Recovered 685' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED 4-24-97 observe this plugging.

Signed Kevin D. Strick
(TECHNICIAN)

DATE 4-24-97

INV. NO. 48010
4-17