

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-21670-00-00
Spot: SENWNW Sec/Twnshp/Rge: 36-21S-35W
4030 feet from S Section Line, 4030 feet from E Section Line
Lease/Unit Name: WRIGHT Well Number: 1-2
County: KEARNY Total Vertical Depth: 2810 feet

Operator License No.: 5293
Op Name: HELMERICH & PAYNE, INC.
Address: 1579 E. 21ST ST.
TULSA, OK 74017

Conductor Pipe: Size feet: 891.33
Surface Casing: Size 8.625 feet: 305 WITH 165 SX CMT
Production: Size 5.5 feet: 2802 WITH 525 SX CMT
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 04/10/2002 2:00 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 400# HULLS & 25 SX MUD SPACER TO 1000'. PUMP CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEVIN STRUBE Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 04/10/2002 4:00 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2734'. PERFS AT 2592-2634'. PUMPED DOWN 5 1/2" CASING 500# HULLS MIXED WITH MUD AND 25 SX CMT. MUD SPACER TO 1000'. PUMP CMT TO SURFACE WITH 125 SX CMT. CMT AT SURFACE. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS 20 SX CMT. MAXIMUM PRESURE 500#. SHUT IN AT 500#.

RECEIVED
APR 21 2002
KCC WICHITA
4-21-02

Remarks: USED COMMON CEMENT BY SARGENTS. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed Kevin Strube
(TECHNICIAN)

INVOICED
APR 17 2002
DATE 4-23-02
INV. NO. 2002061687 NP


FORM EP-2/3