

1 050736

API NUMBER 15- 093-20,845-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NW NW , SEC. 34 , 'T 21 S, R 35 W/EX  
4620 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952

Operator: Amoco Production Company  
Name & Address: P. O. Box 432  
Liberal, KS 67901

Lease Name Horton Well # 1  
County Kearny 152.75  
Well Total Depth 4700 Marmaton feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 1640

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382

Address P. O. Box 916, Garden City, KS 67846

Company to plug at: Hour: 12:00 pm Day: 8 Month: December Year: 19 85

Plugging proposal received from Jennifer Sanders

(company name) Amoco (phone) 316-624-6241  
Elevation 3100'

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1600'

- 1st plug at 4400' with 30 sx cement
- 2nd plug at 2750' with 120 sx cement
- 3rd plug at 1636' with 120 sx cement  
solid bridge
- 4th plug hulls - plug at 40' -- cement to surface with 15 sx cement
- 6th plug to circulate rat hole with 4 sx cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:00 pm Day: 8 Month: December Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 4400' with 30 sx cement, 2nd plug at 2750' with 120  
sx cement, 3rd plug at 1636' with 120 sx cement, 4th & 5th plugs - solid bridge - hulls -  
plug at 40' -- cement to surface with 15 sx cement, 6th plug to circulate rat hole with  
4 sx cement.

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton.  
(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE JAN 07 1986  
11 867

JAN 6 1986 Signed Richard W. Lacey / rjl  
(TECHNICIAN)  
CONSERVATION DIVISION  
Wichita, Kansas

CARD MUST BE TYPED

NOTICE OF INTENTION TO DRILL  
State of Kansas  
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 11 22 85  
month day year

API Number 15- 093-20,845-0000

OPERATOR: License # 5952  
Name Amoco Production Company  
Address P. O. Box 432  
City/State/Zip Liberal, KS 67901  
Contact Person P. A. Lehrman  
Phone 316-624-6241

C NW NW Sec 34 Twp 21 S, Rge 35  
(location) 4620 Ft North from Southeast Corner of Section  
4620 Ft West from Southeast Corner of Section  
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # To be bid  
Name Cheyenne Drilling  
City/State

Nearest lease or unit boundary line 4620 feet.  
County Kearny  
Lease Name Horton Well# 1  
Domestic well within 330 feet:  yes  no  
Municipal well within one mile:  yes  no

Well Drilled For: Well Class: Type Equipment:  
 Oil  Swd  Infield  Mod Rotary  
 Gas  Inj  Pool Ext.  Air Rotary  
 OWWO  Expl  Wildcat  Cable

Depth to Bottom of fresh water 580-125 feet  
Lowest usable water formation Dakota  
Depth to Bottom of usable water ~700 to 900 feet  
Surface pipe by Alternate: 1  2   
Surface pipe to be set 1600 feet  
Conductor pipe if any required None feet  
Ground surface elevation 3100 feet MSL  
This Authorization Expires 5-13-86  
Approved By 11-13-85

If OWWO: old well info as follows:  
Operator  
Well Name  
Comp Date Old Total Depth  
Projected Total Depth 4700 feet  
Projected Formation at TD Cherokee  
Expected Producing Formations Marmaton

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

11-5-85 Signature of Operator or Agent P.A. Lehrman P.A. Lehrman Title Admn. Supvr.  
Form C-1 4/84

Moved in 11-27-85 Spud 28th will call after surface

PUSHER Jennifer Sunder  
TD 4700 FORMATION Marmaton  
SURFACE PIPE 9 7/8 @ 1640  
ANHYDRITE 1600 ELEVATION 3100  
STARTING TIME & DATE Noon 12/9/85  
COMPLETION TIME & DATE 4:00 12/9/85  
1st PLUG @ 4400 FT. W/ 30 SX  
2nd PLUG @ 2750 FT. W/ 120 SX  
3rd PLUG @ 1636 FT. W/ 120 SX  
4th PLUG @ 40 FT. W/ 15 SX  
RAT HOLE CIRCULATED W/ 4 SX  
MOUSE HOLE CIRCULATED W/ SX  
WATER WELL PLUGGED W/ SX  
CEMENT COMPANY Halliburton  
TECHNICIAN  
60/40 2% gel 3% c

JAN 6 1986  
OIL & GAS COMMISSION  
REGISTRATION DIVISION