

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-00259-00-00
Spot: C Sec/Twnshp/Rge: 34-21S-35W
2640 feet from N Section Line, 2640 feet from E Section Line
Lease/Unit Name: ROSS Well Number: 1
County: KEARNY Total Vertical Depth: 2830 feet

Operator License No.: 5952 11/8
Operator Name: AMOCO PRODUCTION COMPANY Conductor Pipe: Size _____ feet:
Address: 2225 WEST OKLAHOMA AVENUE Surface Casing: Size 8.625 feet: 1002 WITH 500 SX CMT
ULYSSES, KS 67880 Production: Size 5.5 feet: 2798 WITH 200 SX CMT
Liner: Size _____ feet: _____ 91.98

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/08/2000 1:30 PM
Plug Co. License No.: 5287 Plug Co. Name: HALLIBURTON SERVICES
Proposal Rcvd. from: SPANKY Company: AMOCO Phone: (316) 356-6955

Proposed Plugging Method: PUMP DOWN 5 1/2" CASING 250# HULLS AND 40 SX CMT. DISPLACE WITH 35 BBL WATER. SET CIBP @ 1030'. PERFORATE AT 1010'. PUMP 190 SX CMT. CIRCULATE TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/08/2000 4:30 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PERFS AT 2628-62, 2696-2708, 2751-74'. PUMPED DOWN 5/2" CASING 250# HULLS & 40 SX CMT. DISPLACED WITH 35 BBL WATER. SET CIBP @ 1030'. PERFORATED @ 1010'. PUMPED 190 SX CMT. CIRCULATED TO SURFACE.

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 2000

CONSERVATION DIVISION
Wichita, Kansas

Received 11-15-00

Remarks: USED 65/35 POZMIX 6% GEL BY HALLIBURTON. NO CASING RECOVERED.

Plugged through: CSG

District: 01

Signed

Kevin Strube
(TECHNICIAN)

INVOICED

DATE 11/21/00

NOV 15 2000

Form CP-2/3

INV. NO. 2001061002

MP