

To: 1 040842
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-29

TECHNICIAN'S PLUGGING REPORT

Operator License / 5422
Operator: Abercrombie Drilling
Name:
Address 150 N. Main, Ste. 801
Wichita, KS 67202

API NUMBER 15-093-21,368-0000
NW NW SE, SEC. 3, T. 21 S, R. 35 W/E
2310 feet from S section line
2310 feet from E section line
Lease Name Crist "C" Well # 1
County Kearny
Well Total Depth 5040 163.80 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 268

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Abercrombie RTD, Inc. License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202

Company to plug at: Hour: 9 a.m. Day: 29 Month: 4 Year: 19 94

Plugging proposal received from Gary

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2279-93'

- 1st plug at Hugoton/Council Grove with 100 sx cement,
- 2nd plug at 2300' with 50 sx cement, 3rd plug at 1150' with 80 sx cement,
- 4th plug at 600' with 50 sx cement, 5th plug at 300' with 50 sx cement, 6th plug at 40' w/10 sx,
- 7th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:45 a.m. Day: 29 Month: 4 Year: 1994

ACTUAL PLUGGING REPORT 1st plug at 3000' with 100 sx cement;
2nd plug at 2300' with 50 sx cement, 3rd plug at 1150' with 80 sx cement,
4th plug at 600' with 50 sx cement, 5th plug at 300' with 50 sx cement,
6th plug at 40' with 10 sx cement,
7th plug to circulate rathole with 15 sx cement.

5-4-94

RECEIVED STATE CORPORATION COMMISSION

MAY 04 1994

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/2# Flozeal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE MAY 05 1994
INV. NO. 40384
4-29

Signed Stephen J. Pfeifer (TECHNICIAN)

