

1 051267

1-31 15.055.10145.0001

372  
P

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-Docket #E-9779  
C SE, SEC. 27, T 21 S, R 34 W/E  
1320 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6234

Lease Name Gobleman "A" Well # 7

Operator: Petroleum Production Management, Inc.  
Name & Address: 209 East William, Suite 200  
Wichita, KS 67202

County Finney 153.08  
Well Total Depth 4710 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 229

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number

Address Liberal, KS

Company to plug at: Hour: 1:30 p.m. Day: 31 Month: 1 Year: 19 90

Plugging proposal received from Steve Park

(company name) Petroleum Production Management, Inc. (phone) 316-265-4651

were: 5 1/2" at 4649' PBD 4320' Perfs at 4280-4292' Well was squeezed at 3119' w/385 sx cement  
1st plug sand back to 4260', cement to 4225',

2nd plug shoot casing at 440', run tubing to 440', circulate cement back up to surface.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:45 p.m. Day: 31 Month: 1 Year: 1990

ACTUAL PLUGGING REPORT 1st plug sanded back to 4260', cemented to 4225',

Pipe collapsed at 443', shot the casing at 440', ran tubing to 440',

2nd plug circulated cement back to surface up 5 1/2" and 8 5/8", used 150 sx light cement.

STATE CORPORATION COMMISSION

FEB 2 1990 2-2-90

NOTE: 8 5/8" was shot off at 30' in 1956.

CONSERVATION DIVISION

Wichita, Kansas

Remarks: Used light cement by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If possible, observe this plugging.)

DATE 2-12-90

Signed Richard M. Lacey  
(TECHNICIAN)

SLM

INV. NO. 27419