

1 090273

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 055-20,575-0000

C NW NE, SEC. 11, T 21 S, R 34 W/X

4620 feet from N/S section line

1980 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Dyer Well # 1

Operator: Berexco, Inc.

County Finney 160.07

Name & Address 970 Fourth Financial Center

Well Total Depth 4925 feet

Wichita, KS 67202

Conductor Pipe: Size            feet

Surface Casing: Size 8 5/8 feet 466

Abandoned Oil Well            Gas Well            Input Well            SWD Well            D&A X

Other well as hereinafter indicated           

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 E. Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 9:00 pm Day: 12 Month: January Year: 19 85

Plugging proposal received from Stan Wyckoff

(company name) Beredco (phone) 316-265-2856

were:            to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1890' with 50 sx cement

2nd plug at 1020' with 50 sx cement

3rd plug at 510' with 40 sx cement

4th plug <sup>solid bridge</sup> hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement Plugging Proposal Received by R Bearhutton (TECHNICIAN)

Plugging Operations attended by Agent?: All            Part            None X

Operations Completed: Hour: 9:45 pm Day: 12 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1890' with 50 sx cement, 2nd plug at 1020' with 50

sx cement, 3rd plug at 510' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement, 7th plug to circulate mouse hole with 10 sx cement

RECEIVED  
STATE CORPORATION COMMISSION  
1-15-85  
JAN 15 1985

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun # 205539  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED I (did/did not) observe this plugging.

DATE 1-18-85

Signed R Bearhutton (TECHNICIAN)

INV. NO. 6583 FEB 18 1985

1-12