

1051038

4-15-88

106 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19-055-20,060-0000
C. NW SE, SEC. 11, T. 21 S, R. 34 W/X
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5131

Lease Name Fleagle "A" Well # 1

Operator: Thunderbird Drilling, Inc.

County Finney 158.41

Name & Address Box 97

Well Total Depth 4874 feet

Ellinwood, KS 67526

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 420

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 2 p.m. Day: 15 Month: 4 Year: 19 88

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 5 1/2" at 4737' PBTD 4703' Perfs at 4354-60'

1st plug sand back to 4300' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 50 sx cement, 10 sx gel, 1 sx hulls and 120 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 p.m. Day: 15 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 50 sx cement, 10 sx gel, 1 sx hulls and 120 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

APR 19 1988

4-19-88

Maximum pressure 800 psi and shut in 350 psi.

Remarks: Used 65/35 Pozmix 6% gel by Allied Conservation Division Wichita, Kansas used 700' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(add xxxxxx) observe this plugging.

DATE 4-26-88

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 20471